

# PROPOSAL

**500,000 GALLON ELEVATED SPHEROIDAL WATER TANK EXTERIOR OVERCOAT**  
**VILLAGE OF OAKBROOK, TERRACE**  
**17W201 ROOSEVELT RD., OAKBROOK TERRACE, IL 60181**

---

April 14, 2022

Proposal #: Q01-04142022

We hereby submit specifications and estimates for the exterior overcoating of the 500,000 Gallon Elevated Spheroidal Water Tank owned by the Village of Oakbrook Terrace, IL as follows:

**1. SURFACE PREPARATION:**

- 1.1. Rig tank per OSHA Standards
- 1.2. Prepare exterior surfaces with 5,000 psi water to remove chalking and loose paint, mold, mildew, dirt, and other deleterious materials.
- 1.3. All areas of corroded metal and loose coatings shall be power tool cleaned per SSPC SP-11. Loose existing coatings shall be feathered back to a tight edge.

**2. COATINGS:**

**2.1. Spot Prime Coat:**

- 2.1.1. To properly prepared bare metal surfaces, apply one spot prime coat Tnemec Series 135 Chem-Build surface tolerant epoxy coating @ 4.0-6.0 mils DFT.

**2.2. Intermediate Coat:**

- 2.2.1. To all surfaces, apply one full intermediate coat Tnemec Series 73 Endurashield aliphatic acrylic polyurethane coating @ 2.0-3.0 mils DFT.
  - 2.2.1.1. Color: TBD

**2.3. Finish Coat:**

- 2.3.1. To intermediate coated surfaces, apply one full finish coat Tnemec Series V700 HydroFlon advanced thermoset solution fluoropolymer coating @ 2.0-3.0 mils DFT.
  - 2.3.1.1. Color: To match existing

**2.4. Lettering/Logo:**

- 2.4.1. Re-apply existing logo and lettering with one coat Tnemec Series V700 HydroFlon advanced thermoset solution fluoropolymer coating @ 2.0-3.0 mils DFT.
  - 2.4.1.1. Color: To match existing

<b>COST FOR THIS WORK: \$127,020.00</b>
-----------------------------------------

**Additional Work:**

1. Additional cost to rent manlift to access stem area if existing antennas are not removed:

<b>Additional Cost for this Work: +\$9,715.00</b>
---------------------------------------------------

---

**CLARIFICATIONS:**

1. Owner to drain tank before start of work.
2. The base proposal assumes all antennas are removed prior to the start of work. Antenna removal to be performed by others at no cost to Jetco, Ltd.
3. No full containment will be necessary. Work shall be coordinated so as to minimize impact on neighboring properties.
4. Owner to provide Jetco with 110v/20A and 220v/30A (single phase) power supply at no cost.
5. Owner to provide water for pressure washing at no cost.
6. General Liability, Umbrella Liability(\$10M), Pollution Liability (\$1M) and Workman's Compensation/Employer's Liability Insurance is included with Village of Oakbrook Terrace named as additional insured (where applicable) and Certificate Holder.
7. Prevailing Wage with Certified Payroll submitted with invoiced pay request.
8. Jetco, Ltd. is a proud member of the International Union of Painters and Allied Trades DC30. All employees are Union trained in craftsmanship and safety including, but not limited to, Lead Paint Removal, Fall Prevention, Respiratory Protection, Personal Protective Equipment and Hazard Communication.
9. Includes Performance and Payment Bonds to cover the work.
10. Includes one year warranty on material and workmanship.
11. All work to be completed within 30 calendar days, excluding delays caused by weather or other circumstances beyond our control.

---

*We propose* hereby to furnish materials and labor – complete in accordance with specifications, for the lump sum of:.....**See Above**

**Payment** to be made as follows: Upon Completion

---

All material is guaranteed to be as specified. All work to be completed in a workmanlike manner according to standard practices. Any alteration or deviation from specifications involving extra costs will be executed only upon written orders and will become an extra cost over and above the estimate. All agreements contingent upon strikes, accidents or delays beyond our control. Owner to carry fire and other necessary insurance. Our workers are fully covered by worker's compensation insurance.

**Authorized Signature:** \_\_\_\_\_  
Kenneth Brend / Superintendent

Note: This proposal may be withdrawn if not accepted within **60** days.

---

**Acceptance of Proposal** – The above prices, specifications and conditions are satisfactory and are hereby accepted. You are authorized to do the work as specified. Payment will be made as outlined above.

Signature: **X** \_\_\_\_\_ Date: \_\_\_\_\_